



FY 2024-25 East Basin Causeway Removal

Addendum #1

Scope of Work

The Invitation to Bid (ITB) lists details of the causeway components to be removed under this project on page three of the ITB. As discussed at today's pre-bid meeting, this project does not include piling removal. Please see the updated scope of work below.

East Basin Marina - Causeway Removal

- Remove concrete and timber structure from failed causeway
- Transfer of debris material for landside disposal
- Contractor to implement best management practices for containment and environmental considerations

The Project allows for the removal of approximately 600ft of failed causeway structure. It includes the removal of failed concrete deck and deteriorating components (including posts, sill plates, railing, wood deck planks, girders, caps, posts, cross members, miscellaneous utilities, et cetera) in accordance with the Port of Astoria's current maintenance permits.