



# FY 2024-25 East Basin Causeway Removal

## Addendum #2

### Questions and Answers

- 1. Are any other construction projects scheduled for the marina during this project window?**  
*Yes. The Port has issued an Invitation to Bid for the dredging in the East Basin.*
- 2. If large debris are uncovered what is the procedure?**  
*If large debris is encountered, the contractor is advised to leave it in place, mark the location, and notify the Port.*
- 3. Can the boat ramp be closed for the duration of the project to minimize boat traffic in the work area?**  
*No. The boat ramp can be closed for short periods of time if deemed necessary.*
- 4. Is the contractor responsible for removal of existing submerged debris? If so, what quantities should be assumed.**  
*Yes. Approximate quantity for submerged debris is a 100ft X 34ft section of collapsed causeway and supporting structure.*
- 5. On the first page of the contract (page 14 of the ITB), one of the components of work is described as "Transfer of debris material for landside disposal". It does not mention any further handling or disposal that should be included in this bid. Is the contractor responsible for processing and disposal of demolition debris? If not, where does the Port wish to have this demolition debris placed?**  
*Yes, the contractor is responsible for processing and disposal of demolition debris.*
- 6. On the underside of the causeway, under the asphalt- is the decking just wood or is there a steel plate under the asphalt?**  
*There are no steel plates. The causeway deck was built using a mixture of treated and untreated wood with a concrete deck.*
- 7. Attachment A from Dept of State Lands line # 3 indicates work below the highest tide on the Columbia River for fill or removal must be conducted between September 24<sup>th</sup> of 2021 To February 28<sup>th</sup> 2022 and November 1<sup>st</sup> to February 28<sup>th</sup> of the following year. What is the in-water work window for this project?**  
*The in-water work window for the causeway removal is November 1, 2024, to December 31, 2024.*
- 8. Can the contractor set up a temporary pile?**  
*Yes, spud piles may be used.*